BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No. 140

Name of the Work : Construction of culverts and drains in Kalapp Layout, Muneshwara Layout and Gopalappa Garden in ward no 10 Doddabommasandra

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	27.14	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50 m and removing the debris to a distance upto 200m, **No. 235/ Item No. 37.48 PWD SR 2010-11**	Cum	127.44	
2	192.96	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 **No. 126/ Item No. 19.2/ PWD SR 2010-11**	Sqm	77.76	
3	165.83	Removing B.S Slab of Drain and stacking **Page No. 24/ Item No. 5.32/ PWD SR 2010-11**	Cum	42.77	
4	36.18	Providing and laying in position **plain cement concrete of nominal mix 1:4:8 using 40mm** and down size graded granite metal machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ **Item No. 4.3/ PWD SR 2010-11**	Sqm	3495.96	
5	8.14	KSRB 5.2-2 Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6,** stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 **Page No. 22/ Item No. 5.6/ PWD SR 2010-11**	Sqm	1745.81	
6	72.66	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 **Page No. 22/ Item No. 5.9/ PWD SR 2010-11**	Cum	3075.84	
7	19.60	KSRB 4-1.7 : Providing and laying in position **plain cement concrete of nominal mix 1:2:4 using 20mm** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. **No. 12/ Item No. 4.6/ PWD SR 2010-11**	Cum	4664.52	
8	120.60	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. **Page No. 97/ Item No. 15.1 / PWD SR 2010-11**	Cum	67.28	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
9	79.35	KSRB 4-6.2 Providing and removing centering, shuttering, strutting, propping etc.,and removal of form work for all flat syrface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200mm including cost of all materials, labour complete as per specifications.(P No. 14 Item No.4.29 PWD SR 2010-11)	Cum	237.60	
10	45.07	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of nominal mix 1:1.5:3 with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, **No. 12/ Item No. 4.11/ PWD SR 2010-11**	Cum	5247.72	
11	40.57	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **Page No. 16/ Item No. 4.46/ PWD SR 2010-11**	Sqm	5838.48	
12	246.99	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	cum	67.32	

Signture of the Contractor

ಕರದು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .04.(-)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಯಲಹಂಕ ವಲಯ
ಬೆಂಗಳೂರು 560092

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92